

# The 32T

A stylized graphic of a fan or turbine, composed of a grid of blue and black segments arranged in a semi-circular pattern. The segments are arranged in a grid that tapers towards the center, creating a sense of depth and rotation. The blue segments are on the right side, and the black segments are on the left side. The overall shape is a semi-circle with a central hub.

# The Approach to 32T

- A necessary development phase in getting to the 512T
- An engineering test-bed
  - Check out the hardware & firmware (+ software) performance
  - Iron out the interfaces and system integration aspects
  - Get field experience
  - Learn more about the operating environment, sky, ionosphere, ...
  - An opportunity for things we did not think about to crop up
  - Hone our deployment skills and procedures
- We have a tight schedule for the MWA  $\Rightarrow$  the 32T must follow a tight schedule as well
  - Forces one to focus on the key functionality (avoids feature creep)
- The implementation plan follows a phased approach
  - Expected hardware availability schedule
  - Expected infra-structure availability schedule
  - Maximise the learning/returns from the effort
  - Common sense

# Some Guiding Principles


- Maximise environmental exposure to hardware
- Test, debug and verify all interfaces in lab prior to field installation
- Exercise the system enough to learn from it and for strains and cracks to show up
- Identify key questions and conduct focused observing campaigns
- Learn in time to feed into the MWA development process

# 32T Specs

- 32 tiles, 4 nodes
- Collecting area  $\sim 550 \text{ m}^2$  ( $\sim 1$  VLA dish, 6.25% of full array)
- Bandwidth – 32 MHz
- $\Delta t = 62.5 \text{ ms}$
- $\Delta \nu = 80 \text{ kHz}$
- longest baseline  $\sim 350 \text{ m}$  ( $\sim 15'$  @ 200 MHz)
- 496 physical baselines (0.4% of full array)
- Max data rate  $\sim 12.7 \text{ Mvis/s}$  (UVFITS  $\sim 100 \text{ MBytes/s}$ )
- Power consumption  $\sim 10 \text{ kW}$  (includes HVAC in Control Facility)

# 32T Configuration

- Randomised Reuleaux triangle
  - Well sampled, reasonably uniform uv coverage
- Tile spacings along the arm vary in a log manner
- Longest baseline ~350m
- Distance between vertices 200m
- Optimisation in progress




# 32T expectations

- All 32 tiles to be deployed in one go
- Estimate of effort involved ~25 days for one 2 person crew (survey + ground preparation + deployment + preliminary testing + 20% contingency)
  - Assumptions – No trenching, minimal ground preparation
- 8T
  - 1<sup>st</sup> receiver on bench, reduced functionality
  - A data capture device and offline correlation, limited bandwidth
- 32T
  - 4 receivers, subsequent receivers closer approximations to the final design in functionality and packaging
  - On site hardware correlator
- Connect beam-formers to receiver by coax running on the ground
- Receivers and Correlator sit next to each other in a trailer
- Upgrades to firmware functionality over time
- 32T expected to functional well into the 512T regime, as an engineering test bed and eventually as a high time resolution instrument

# Infrastructure requirements

- Lab and office space (trailer?)
- Living space (mobile home, donga?)
- Power generation and fuel supply
- Internet connection to the outside world

# 32T target timeline



# Ongoing efforts

- Logistics of system integration, testing and debugging
- EMC enclosure for Node hardware and correlation
- Computing hardware requirement
- M&C software (minimal functionality)
- Refine list of issues to be addressed by the 32T
- Observing plan
- Post processing software
- Data archiving and access
- ...



# The 32T planning and execution

- We are all convinced that
  - We need 32T
  - The time scale seems doable
- $32 \ll 512$ ... but
  - Will eventually involve every sub-system of

Our prime asset

- A talented and energetic team
- Demonstrably impressive pace of work
- The will to push forth and take on the problems

# My role

- Coordinator
- Provide a skeleton implementation plan, seek inputs from appropriate people to flesh out
- Keep a system wide perspective on the state of things
- Look out for problems, schedule impacts, inconsistencies and gaps in planning
- Organisational glue, communications, ...

# The outcome

- Get to a more complete task list
- Identify a person(s) for each of the tasks
  - Contribute to formulating a detailed plan for the task, coordinate with others if needed
  - Do what is necessary to execute the plan
  - Identify potential problems
  - Raise flags before they become real problems
  - Be the contact person for information regarding the task

# Site

- Identifying the land on which MWA will appear
  - Permissions
  - Initial survey of potential sites – Merv, 07/16/07
    - First survey of the circular regions in Tony's polygon + perhaps another region
  - Coordination with ATNF about locations of ASKAP, MWA and central building – Boolardy Site Coordination Group
    - Infrastructure sharing (common building, power generation, optical fiber pipe out of Boolardy,...)

# Infrastructure

- Compile a list of requirements (accommodation, lab/office space, power requirements) and time scale – Bob Sault
- Communicate/coordinate with ATNF
- Identify concerns, looks for solutions/work arounds – Bob Sault

# Tile

- Dipoles – Brian Corey
- Ground-screens – Brian/Merv/Steve Burns
  - Identify suppliers, lead times, ...
- Beam-formers – Brian Corey
- Cables (co-ax+power) – Brian/Mark Waterson
- Power generation – ED
- Protection against fauna - Brian

# Deployment


- Expedition 1 Goals
  - Deploy as many of the 32 tiles as possible (ground planes + dipoles + lay (few co-ax cables)
  - Test as many of the tiles as possible
    - 2 beam-formers, 1 spectrometer available, set up overnight drift scans 1 tile at a time
- Timeframe – 3<sup>rd</sup>-4<sup>th</sup> wk. Aug
- Estimate volume of work  $\Rightarrow$  size of team, duration of stay (4 people, ~2 wks)
- Identify the team
  - Team leader (someone with prior site experience) – Brian/Divya
  - One technical expert
  - Skill set – task list
  - Special skills (first aid certification, survey, drivers)
  - Team leader to assign responsibilities of local logistics to team members and others
  - Students from (MKI)
  - Mark Derome (Haystack)

# Deployment...

- Equipment list - David Barnes?/Team Leader
  - Procurement
- Installation procedure
  - Tile assembly
  - How do we make sure that we learn from this
- Test procedure(s)
- OHS issues -
- Cultural Sensitivity training (9-15 July) – Bob Sault
- Configuration -Divya Oberoi

# Deployment...

■ Trenching?



# Receiver

- Mark Waterson
- Development Milestones ?
- Raise flags when you have concerns, before they become problems

# Data Capture (8T)/Correlator

- Discussions underway - Roger
  - Decisions made?
- Decision point – availability of the PFB?
  - Early Sep
  - Leave enough time to pursue alternative approaches

# RTS

- UVFITS writer - Randall
- UVFITS format, understood by RTS
  - What can we learn about the tiles
    - How identical are they
    - Beam patterns, stability...
  - Algorithms
    - Convergence, SNR
  - Ionosphere

- EMC Enclosure for – Roger/Ant
  - Receiver
  - Correlator
  - Field installable Faraday rooms -
- Computing hardware requirement
- System integration (Lab/Field) - Roger
  - Tiles – Beamformer
  - Beamformer – Receiver
  - Receiver – Data capture device
  - Receiver – Correlation

# M&C

- Control – Lister/Miguel
- Hardware status and system health
- Simple data checks - Randall
  - Near real time display – matrix of mean,rms of amp, ph on different baselines

- Objectives
  - What sort of observations do we need
  - Observing Plan
  - Analysis Software
- 
- Data formats - Mitch
  - Archive – Frank/Barnes
  - US copy – Ed Morgan

# 1<sup>st</sup> Expedition

- 7<sup>th</sup> Sept, 2 wk
- 7 people
- Deploy 32 tiles
- 2 'old' beamformers + Acquaris spectrometer
  
- Brian, Divya, Mark Derome, Steve Burns, Merv, Dave Herne, Chris

# 2<sup>nd</sup> Expedition

- 7<sup>th</sup> Oct, 2 (?) wks
- 4 people
- 8 'new' beamformers
- 1<sup>st</sup> receiver
- Data capture device
- Frank\*, Mark Waterson, Roger, Colin

# 3<sup>rd</sup> Expedition

- 15<sup>th</sup> Nov, 2(?) wks
- 4 people
- More observations
  
- Univ. of Melb.

# 4<sup>th</sup> Expedition

- 1<sup>st</sup> wk Jan
  - # of people
  - Remaining beamformers
  - 3 Receivers
  - The correlator
- 
- Roger, Bart, Divya\*, Miguel\*, Jackie\*, Alan Whitney, Mike

# 32T target timeline

